

**Residential Apartment Row Development in  
Buckhead, Atlanta**

**Project Manager : Timi Ogunjobi  
timiasservice@gmail.com**

# Business Case

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

**Prepared by:** Timi Ogunjobi

**Date:** 07/01/2021

## Executive Summary

Big Homes Construction LLC proposes the development of a residential apartment row in Buckhead to capitalize on Atlanta's growing demand for upscale rental housing. The project will offer 150 units equipped with modern amenities while incorporating sustainable practices, aiming for LEED Silver certification.

## Project Objectives

1. **Financial Goals:** To generate a stable, long-term income stream with an estimated annual revenue of \$3 million.
2. **Market Positioning:** Create a modern, eco-friendly residential option that aligns with the lifestyle needs of upper-middle-income professionals and families.
3. **Community Value:** Contribute positively to Buckhead's development by offering high-quality housing and fostering sustainable living.

## Cost-Benefit Analysis

- **Total Projected Costs:** \$20 million
  - **Direct Construction Costs:** \$15 million
  - **Permits, Legal, and Administrative Costs:** \$2 million
  - **Marketing and Lease-Up Costs:** \$1 million
  - **Contingency:** \$2 million (10%)
- **Projected Annual Income:** \$3 million
- **Estimated ROI:** 10% per year with a payback period of 7 years.

## Key Benefits

1. **Financial Return:** Generates consistent income and increases property value.
2. **Sustainable Development:** The project aims to achieve LEED Silver, setting a benchmark for green building standards in the area.

3. **Community and Economic Boost:** Local job creation, increased property values, and added housing inventory to meet demand.

### **Justification**

The Buckhead district is primed for growth in the upscale residential sector. The project is strategically positioned to cater to a rising demand for environmentally responsible housing while ensuring steady revenue for Big Homes Construction LLC.

# Project Charter

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

**Project Manager:** Timi Ogunjobi

**Sponsor:** Big Homes Construction LLC

**Date:** TBD

## Project Goals

1. **Develop a high-quality, modern residential apartment complex** in Buckhead, targeting upper-middle-income residents.
2. **Enhance local community aesthetics** and provide sustainable housing options.
3. **Achieve profitability** within the first five years post-construction by maintaining high occupancy rates and offering competitive rental prices.

## Scope

- **Location:** Buckhead district, Atlanta, on Lenox Road.
- **Project Duration:** 18 months, from initial ground-breaking to final inspection.
- **Components:**
  - 150 residential units with amenities such as a pool, gym, coworking space, and rooftop terrace.
  - Parking facilities for residents and guests.
  - Landscaping and green spaces to promote sustainability.
  - LEED Silver certification through sustainable building materials and energy-efficient systems.

## Project Objectives

1. **Timely Completion:** Complete the project within 18 months, with structured milestones for phases such as permitting, foundation, structural, and finishing.
2. **Within Budget:** Keep total costs within the allocated budget of \$20 million, including a 10% contingency for unexpected expenses.
3. **Quality Standards:** Maintain high construction standards and comply with city and environmental regulations.
4. **Community Engagement:** Work closely with local authorities and neighborhood

associations to ensure minimal disruption to the community.

## **Stakeholders**

- **Project Sponsor:** Big Homes Construction LLC – Oversees funding and expects timely, high-quality deliverables.
- **Project Team:** Architects, engineers, construction crews, suppliers, and subcontractors.
- **Local Government and Regulatory Authorities:** In charge of permits and regulatory approvals.
- **Future Residents:** Primary end-users of the facility, expecting a high-quality, sustainable living experience.
- **Local Community Organizations:** Interested in minimizing construction disruption and ensuring the project contributes positively to the area.

## **Success Criteria**

- Project delivered on time and within budget.
- All necessary permits obtained and inspections passed without major delays.
- Achieve a 90% occupancy rate within the first year.
- Maintain LEED Silver certification upon completion.

# Scope Statement

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

## 1. Project Purpose and Justification

This project aims to develop a modern, sustainable residential apartment complex in Buckhead, Atlanta, catering to the demand for high-quality, eco-friendly housing for young professionals and small families. The development will enhance the local real estate market, meet sustainable building goals through LEED Silver certification, and provide an attractive community space.

## 2. Project Description

The project includes constructing a 150-unit residential building with modern amenities and community spaces. The development will span over [specific acreage or square footage], with green areas, sustainable landscaping, and energy-efficient systems to meet LEED Silver requirements.

## 3. Deliverables

- **Main Building Structure:**
  - 150 residential units of varying sizes (1-bedroom, 2-bedroom, and 3-bedroom apartments).
  - Common areas, including lobby, coworking spaces, gym, rooftop terrace, and community rooms.
  - Interior finishing with high-quality materials and energy-efficient appliances.
- **Parking and Accessibility:**
  - Underground or adjacent parking facility with spaces for residents and guests.
  - Accessibility features in compliance with ADA (Americans with Disabilities Act) standards.
- **Green Spaces and Landscaping:**
  - Landscaped outdoor areas, walking paths, and seating areas for resident relaxation.
  - Low-maintenance, drought-resistant plants for sustainability.
- **Energy Efficiency and Sustainable Features:**
  - Energy-efficient HVAC systems, lighting, and appliances.
  - Solar panels or alternative green energy sources.

- Water-efficient plumbing fixtures.
- **Compliance and Certification:**
  - LEED Silver certification.
  - Compliance with Atlanta zoning and environmental regulations.

#### 4. Project Boundaries

- **Inclusions:**
  - All structures, facilities, and landscaping as described in the deliverables.
  - All required infrastructure connections (water, sewer, gas, electricity).
  - LEED Silver certification efforts and required documentation.
- **Exclusions:**
  - No commercial spaces within the building (project is strictly residential).
  - No provision for separate retail or external businesses on the property.

#### 5. Constraints

- **Time:** The project must be completed within 18 months from the start date.
- **Budget:** The budget is capped at \$20 million, including all contingency funds.
- **Regulatory:** Must comply with all Atlanta zoning, building, and environmental regulations.

#### 6. Assumptions

- Local authorities will issue necessary permits without delays beyond regulatory processing times.
- Market conditions will remain stable, allowing for consistent procurement of materials.
- LEED Silver certification requirements will not change during the project timeline.
- All subcontractors and vendors will meet quality standards and project timelines.

#### 7. Acceptance Criteria

- **Building Completion:** All units, community spaces, and facilities must be completed per specifications and approved by Big Homes Construction LLC.
- **Quality Standards:** Building should pass all quality and safety inspections and meet LEED Silver certification.
- **Compliance:** All work must comply with the relevant local codes and regulatory requirements.

- **Stakeholder Approval:** Final project approval will require sign-off from Big Homes Construction LLC, regulatory authorities, and quality inspectors.



# Feasibility Study

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

## Overview

The feasibility study for the Buckhead apartment row development evaluates the project's viability by examining financial feasibility, potential risks, environmental impact, and benefits to the community.

## Project Viability

### 1. Financial Analysis

- **Estimated Total Cost:** \$20 million
- **Projected Revenue:** \$3 million annually through rental income.
- **Return on Investment (ROI):** Expected payback within 7 years post-construction based on an average occupancy rate of 85%.

### 2. Market Demand

- **Target Market:** Young professionals and small families within upper-middle-income demographics.
- **Market Analysis:** Buckhead's rental market currently experiences a 90% occupancy rate, with a growing demand for sustainable, community-oriented apartment complexes.

### 3. Regulatory Feasibility

- Permits and approvals needed include zoning approval, environmental clearance, and building permits.
- Building codes mandate adherence to Buckhead's zoning regulations and green construction practices.

## Potential Risks

1. **Market Risks:** Potential decline in demand due to economic downturns.
2. **Construction Risks:** Cost overruns due to unforeseen structural issues or material shortages.
3. **Environmental and Regulatory Risks:** Delays due to environmental regulations or community opposition.

4. **Operational Risks:** Higher maintenance costs for sustainability systems (e.g., energy-efficient HVAC).

### **Impact on Surrounding Area**

#### **1. Positive Impacts:**

- Increases local real estate value and aesthetic appeal.
- Creates construction and post-completion employment opportunities.
- Strengthens the housing market by introducing sustainable, high-quality rental options.

#### **2. Potential Negative Impacts:**

- Increased traffic and congestion during construction.
- Possible noise pollution affecting neighboring residents.

### **Conclusion**

The project is deemed feasible based on financial projections, market demand, and the expected positive impact on the Buckhead community, with mitigation strategies in place to address potential risks.

# Stakeholder Register

Stakeholder	Role	Interest	Influence
Big Homes Construction LLC	Project Sponsor	Financial return, reputation, project success	High
Project Manager	Project oversight	Project success, timely and on-budget completion	High
Architectural Firm	Design lead	High-quality, innovative design, compliance with codes	Medium to High
Construction Contractors	Execution team	Timely project delivery, quality adherence, safety compliance	Medium
Local Government (Zoning and Planning)	Regulatory authority	Compliance with zoning and building regulations	High
Environmental Protection Agency	Environmental oversight	Ensuring sustainable practices, minimizing environmental impact	Medium
Local Community Groups	Community stakeholders	Minimizing disruption, enhancing neighborhood appeal	Medium to High
Future Residents	End users	High-quality, comfortable, eco-friendly living spaces	Low (until lease-up stage)
Real Estate Agents	Marketing and sales	Profitable leasing/sales, community reputation	Medium
Utility Providers	Service providers	Smooth integration of water, gas, electricity services	Low
Suppliers and Subcontractors	Material and service provision	Reliable payment, long-term relationship with Big Homes Construction	Medium

# Project Management Plan

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

**Project Manager:** Timi Ogunjobi

**Sponsor:** Big Homes Construction LLC

**Date:** 07/01/2021

## 1. Scope Management Plan

- **Project Scope:** The project includes the construction of a residential apartment complex featuring 150 units, community spaces, parking facilities, green areas, and LEED Silver certification. Each unit will be equipped with high-quality finishes, sustainable energy-efficient fixtures, and modern amenities.
- **Scope Control:** The project manager will manage and document scope changes through a formal change request process. All changes require written approval from the project sponsor.
- **Deliverables:**
  - Completed 150-unit apartment complex with community amenities
  - Landscaping and green spaces for sustainability and aesthetics
  - Energy-efficient systems, LEED Silver certification

## 2. Schedule Management Plan

- **Project Timeline:** The total project duration is 18 months.
- **Milestones:**
  - Project Initiation: Month 1
  - Design and Permitting Phase: Months 2-4
  - Site Preparation and Foundation: Months 5-6
  - Structural Work: Months 7-10
  - Interior Finishing and Landscaping: Months 11-15
  - Final Inspection and Approvals: Month 16
  - Lease-Up and Marketing: Months 17-18
- **Tools and Techniques:** The project schedule will be managed using project management software such as MS Project or Primavera. The project manager will hold weekly status

meetings and provide monthly progress reports to all stakeholders.

### 3. Budget Management Plan

- **Total Budget:** \$20 million, including a 10% contingency.
- **Cost Categories:**
  - Direct Costs: \$15 million (labor, materials, and equipment)
  - Indirect Costs: \$2 million (permitting, legal fees, administrative expenses)
  - Marketing and Lease-Up Costs: \$1 million
  - Contingency Reserve: \$2 million
- **Budget Control:** The project manager will use earned value management (EVM) to track project costs. Monthly budget reports will be reviewed with the project sponsor, and all budget adjustments require written approval.

### 4. Quality Management Plan

- **Quality Standards:** The project will adhere to the LEED Silver certification standards for energy efficiency and sustainable construction. Quality benchmarks will align with local building codes and Big Homes Construction's internal quality standards.
- **Quality Assurance:** Ongoing inspections will be conducted at each phase of construction by both the project manager and third-party quality inspectors.
- **Quality Control:** A punch list will be completed prior to final inspections, and any defects must be corrected before final project handover.

### 5. Communication Management Plan

- **Stakeholder Communication:** All stakeholders will receive bi-weekly updates, while the project team will conduct daily check-ins on progress.
- **Communication Channels:**
  - **Email:** For formal updates, decisions, and approvals.
  - **Project Management Software:** For real-time schedule and task updates.
  - **In-Person and Virtual Meetings:** Weekly status meetings for project team, bi-weekly sponsor updates, and monthly stakeholder reviews.
- **Reports:**
  - Weekly progress reports to the project team.
  - Monthly project summaries to all stakeholders.
  - Ad-hoc reports for critical issues or urgent changes.

## 6. Risk Management Plan

- **Risk Identification:** Key risks include construction delays, cost overruns, environmental issues, and safety incidents.
- **Risk Assessment:** Risks will be assessed based on probability and impact, with high-priority risks receiving immediate attention.
- **Risk Mitigation:**
  - **Delays:** Buffer times included in schedule.
  - **Cost Overruns:** 10% contingency fund and cost control measures.
  - **Safety:** Adherence to OSHA standards and regular safety training.
  - **Environmental:** Compliance with local environmental regulations.
- **Risk Monitoring:** The project manager will update the risk register monthly and report critical risks to the sponsor as they arise.

## 7. Procurement Management Plan

- **Procurement Requirements:** Major items to be procured include building materials, energy-efficient systems, landscaping services, and interior finishing materials.
- **Vendor Selection:** The project manager will assess and select vendors based on cost, quality, reliability, and compliance with LEED standards.
- **Contract Types:** Fixed-price contracts for material suppliers, time-and-materials contracts for labor.
- **Contract Management:** Regular monitoring of vendor performance and adherence to schedule, with payment milestones tied to deliverables.

## 8. Stakeholder Management Plan

- **Identification and Analysis:** Stakeholders include the project sponsor, construction team, local authorities, future residents, and local community organizations.
- **Engagement Strategy:** Frequent, transparent communication tailored to the needs of each stakeholder group. Community meetings will be scheduled to address any neighborhood concerns.
- **Conflict Resolution:** All issues will be documented in an issue log and addressed promptly. Significant conflicts will be escalated to the project sponsor if necessary.

# Quality Management Plan

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

## 1. Quality Objectives

- Meet or exceed LEED Silver standards to ensure environmental sustainability.
- Deliver all 150 units with high-quality finishes, energy-efficient systems, and modern amenities.
- Ensure all construction work complies with Atlanta building codes and zoning requirements.
- Achieve a defect-free final product with minimal punch list items.

## 2. Quality Standards

- **Materials and Workmanship:** Use durable, high-quality materials approved by project specifications. Workmanship must adhere to industry standards and local codes.
- **Sustainable Design:** Achieve LEED Silver certification by following guidelines for energy efficiency, water conservation, and indoor air quality.
- **Safety Compliance:** All work must comply with OSHA (Occupational Safety and Health Administration) standards and local safety regulations.
- **Regulatory Compliance:** Follow all Atlanta zoning, environmental, and building code requirements.

## 3. Quality Assurance (QA)

- **Pre-Construction QA:** Verify that all materials meet project standards before ordering. Review plans with the project team to identify potential issues.
- **Ongoing QA Checks:** Conduct inspections at each major phase (foundation, framing, plumbing, electrical, finishing) to ensure compliance with quality standards.
- **Documentation:** Keep a detailed quality log for each inspection, noting compliance, deficiencies, and corrective actions taken.
- **Third-Party Inspections:** Hire independent inspectors at critical milestones to validate quality against regulatory and LEED standards.

#### 4. Quality Control (QC)

- **Site Supervision:** Daily supervision to monitor adherence to project specifications and quality standards.
- **Punch List:** Before final completion, compile a list of outstanding items that require correction or improvement.
- **Final Inspections:** Conduct a comprehensive inspection before project handover to ensure that all units and facilities meet quality criteria.
- **Corrective Actions:** Any identified quality issues must be documented and corrected before final sign-off by the project sponsor.



# Risk Management Plan

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

## 1. Risk Identification

The following are the key potential risks identified for this project:

- **Market Risks:** Economic downturns affecting demand for rental properties.
- **Construction Risks:** Cost overruns due to material price fluctuations or unexpected site conditions.
- **Environmental Risks:** Delays caused by adverse weather or environmental compliance issues.
- **Regulatory Risks:** Permits or approvals delayed or denied by regulatory authorities.
- **Safety Risks:** Worker injuries or accidents on the construction site.
- **Operational Risks:** Potential issues with energy-efficient systems leading to higher maintenance costs.

## 2. Risk Assessment

- **Likelihood and Impact:** Each risk is rated based on its probability (Low, Medium, High) and impact (Minor, Moderate, Major).
  - **High-Impact Risks:** Safety incidents, regulatory delays, construction cost overruns.
  - **Medium-Impact Risks:** Weather delays, environmental compliance issues.
  - **Low-Impact Risks:** Market fluctuations, minor operational issues.

## 3. Risk Mitigation Strategies

- **Market Risks:** Monitor market trends; adjust marketing strategy or rental pricing if demand shifts.
- **Construction Risks:** Allocate a 10% contingency fund; maintain good relationships with suppliers for cost stability.
- **Environmental Risks:** Develop a weather contingency schedule and use protective site covers to mitigate delays.
- **Regulatory Risks:** Ensure compliance through early engagement with regulatory bodies; monitor permit application status proactively.

- **Safety Risks:** Implement a strict safety management plan with regular training, daily safety checks, and safety equipment compliance.
- **Operational Risks:** Select reliable, certified energy systems; set up a maintenance fund for unforeseen operational expenses.

#### **4. Risk Monitoring and Review**

- **Risk Register:** Update and review the risk register monthly, or as new risks emerge.
- **Regular Reviews:** Conduct risk review meetings bi-monthly to assess new risks, update existing ones, and implement necessary actions.
- **Escalation Procedures:** Significant risks will be escalated to the project sponsor and stakeholders promptly, with proposed mitigation actions.

# Procurement Management Plan

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

## 1. Procurement Requirements

- **Materials:** Building materials, energy-efficient HVAC systems, solar panels, and interior finishes.
- **Labor:** Skilled labor for construction, plumbing, electrical, and finishing works.
- **Subcontracted Services:** Landscaping, sustainable design consulting, independent quality inspections.
- **Equipment:** Construction equipment rentals as needed for various phases.

## 2. Vendor Selection Process

- **Pre-Qualification:** Screen vendors based on quality, reliability, experience, and compliance with LEED standards. Preference will be given to vendors with proven experience in sustainable construction.
- **Request for Proposals (RFPs):** Issue RFPs for major procurements, including materials, energy systems, and finishing work.
- **Evaluation and Selection:** Each proposal will be evaluated based on price, quality, vendor reputation, and compliance with project standards.
- **Contract Types:**
  - **Fixed-Price Contracts:** Used for bulk materials and subcontracted services to stabilize project costs.
  - **Time-and-Materials Contracts:** For labor and equipment, allowing flexibility for minor adjustments.

## 3. Procurement Schedule

- Procurement will be staggered based on project phases:
  - **Site Preparation and Foundation:** Materials ordered in Month 1, with delivery timed for early construction stages.
  - **Structural Materials:** Ordered in Month 3 to coincide with foundation completion.
  - **Finishing Materials:** Ordered in Month 8, with deliveries staggered to avoid on-site

storage issues.

#### **4. Contract Management**

- **Vendor Performance:** Monitor vendor performance through regular reviews and ensure timely deliveries.
- **Payment Schedule:** Payments will be milestone-based to align with the completion of work phases and quality inspections.
- **Issue Resolution:** Address issues or delays promptly through documented communication and escalation to the project manager if necessary.

# Communications Plan

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

## 1. Communication Objectives

- Ensure timely, accurate information sharing among stakeholders.
- Keep stakeholders updated on project progress, risks, and milestones.
- Facilitate clear, transparent communication to manage expectations and address any issues promptly.

## 2. Communication Methods and Channels

- **Email:** For formal updates, decision-making records, and distribution of reports.
- **Project Management Software:** Real-time updates on tasks, deadlines, and progress visible to the project team and select stakeholders.
- **Meetings:**
  - **Weekly Project Team Meetings:** To discuss progress, address issues, and review the next steps.
  - **Monthly Stakeholder Meetings:** Summarize progress, highlight risks, and present the budget and schedule status.
  - **Ad-Hoc Meetings:** Scheduled as needed for urgent issues or risk escalation.

## 3. Communication Schedule

- **Weekly Status Reports:** Distributed to the project team every Monday, summarizing work completed, current issues, and planned activities.
- **Bi-Weekly Progress Reports:** Distributed to the project sponsor and key stakeholders, covering high-level progress, risks, and financials.
- **Monthly Stakeholder Summary:** Provides detailed updates on milestones, budget, schedule, and quality, shared with all project stakeholders.

## 4. Communication Roles and Responsibilities

- **Project Manager:** Responsible for overall communication management, ensuring information is shared accurately and on time.
- **Project Team Leads:** Provide updates to the project manager, participate in weekly

meetings, and assist in preparing reports.

- **Stakeholders:** Receive regular updates and provide feedback; attend monthly stakeholder meetings.

## 5. Key Messages and Reports

- **Progress Reports:** Detailed weekly and bi-weekly reports covering schedule adherence, cost tracking, risk management, and quality control.
- **Financial Reports:** Monthly budget summaries showing actual vs. planned expenditures.
- **Risk Reports:** Highlight critical risks, mitigation actions, and updates to the risk register.
- **Quality Reports:** Quality control findings and quality assurance updates distributed monthly.

## 6. Feedback and Issue Resolution

- **Feedback Mechanism:** Stakeholders are encouraged to provide feedback through monthly meetings or direct email.
- **Issue Resolution Process:** Issues raised by stakeholders will be documented and addressed by the project manager within two business days, with status updates provided as needed.

# Environmental Impact Assessment (EIA)

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

**Prepared by:** Enviroconsult America

**Date:** 06/06/2021

## 1. Project Overview

The proposed Residential Apartment Row Development in Buckhead, Atlanta, involves constructing a 150-unit residential apartment complex with community amenities, green spaces, and energy-efficient systems. The project is intended to provide sustainable housing for upper-middle-income residents while achieving LEED Silver certification. This Environmental Impact Assessment (EIA) analyzes potential environmental impacts and outlines mitigation strategies to minimize adverse effects on the surrounding area.

## 2. Environmental Baseline

- **Project Location:** The site is located in a mixed-use area in the Buckhead district of Atlanta, surrounded by residential and commercial properties. The terrain is relatively flat, with minimal natural vegetation on-site.
- **Local Ecology:** The project area does not contain any protected species, wetlands, or high-value ecological zones. Existing vegetation includes grass and sparse trees, which will be partly retained and supplemented by new landscaping.
- **Air and Water Quality:** Current air and water quality levels meet Atlanta's regulatory standards. There are no bodies of water on the site, and it is not located within a floodplain.

## 3. Potential Environmental Impacts

### A. Air Quality

- **Impact:** Construction activities, including excavation, concrete work, and transportation, are likely to generate dust, particulate matter, and emissions from construction equipment.
- **Mitigation:** Employ dust suppression techniques, including regular site watering and installing dust barriers. Use low-emission construction equipment to minimize air pollution.

### B. Noise Pollution

- **Impact:** Noise from construction equipment and activities may disrupt nearby residents and businesses, especially during peak construction phases.

- **Mitigation:** Limit high-noise activities to daytime hours. Install noise-dampening barriers along the perimeter to reduce noise pollution.

### C. Water Management

- **Impact:** Increased runoff from the construction site may carry sediments and pollutants to nearby stormwater drains, potentially affecting water quality downstream.
- **Mitigation:** Implement an erosion and sediment control plan, including silt fences and sediment traps. Use low-impact landscaping and permeable materials to minimize runoff.

### D. Soil and Land Use

- **Impact:** Excavation and foundation work will disturb existing soil, potentially leading to soil erosion and loss of ground cover.
- **Mitigation:** Stabilize soil with vegetation after construction, and use erosion control mats during construction to prevent soil displacement.

### E. Waste Management

- **Impact:** Construction activities will generate solid waste, including debris, packaging, and construction materials.
- **Mitigation:** Implement a waste management plan that includes sorting, recycling, and proper disposal of materials. Coordinate with licensed waste disposal contractors to minimize environmental impact.

### F. Energy Use

- **Impact:** High energy consumption during construction due to the use of heavy machinery and temporary lighting.
- **Mitigation:** Use energy-efficient equipment and schedule energy-intensive tasks during off-peak hours when possible.

### G. Local Flora and Fauna

- **Impact:** Minor impact on local flora due to the removal of trees and vegetation for construction purposes.
- **Mitigation:** Replant trees and add native vegetation as part of the landscaping plan, with a commitment to maintaining greenery post-construction.

## 4. Positive Environmental Impacts

- **Sustainable Building:** LEED Silver certification will ensure that the building meets high sustainability standards, including energy efficiency, reduced emissions, and water conservation.
- **Green Spaces:** The development will incorporate green spaces and landscaping, creating



urban greenery for residents and contributing positively to local air quality and aesthetics.

- **Reduced Carbon Footprint:** Installation of energy-efficient HVAC systems and solar panels will reduce the complex's carbon footprint over its lifecycle.

## 5. Monitoring and Compliance

- **Regular Inspections:** Environmental consultants will conduct regular inspections throughout construction to ensure compliance with mitigation measures.
- **Reporting:** Monthly environmental compliance reports will be submitted to local authorities, including updates on air quality, noise levels, waste management, and any corrective actions taken.
- **Post-Construction Monitoring:** Conduct a post-construction environmental review to assess the effectiveness of mitigation measures and ensure that all final landscaping and green features are properly installed.

## 6. Conclusion

The Environmental Impact Assessment concludes that, with proper mitigation measures, the project's potential environmental impacts can be effectively managed. The project will ultimately contribute to the local area's sustainability goals and enhance urban greenery in Buckhead.

# Permits and Approvals

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

## 1. Building Permits

- **Description:** A building permit is required from the City of Atlanta to authorize construction work on the residential complex.
- **Agency:** City of Atlanta Department of City Planning, Office of Buildings.
- **Documents Required:**
  - Construction drawings and architectural plans.
  - Structural, electrical, and plumbing plans.
  - Fire safety and accessibility plans.
- **Approval Timeline:** Typically takes 4-8 weeks from submission.

## 2. Zoning Approvals

- **Description:** Zoning approval is necessary to confirm that the proposed residential development aligns with the zoning regulations for the Buckhead district.
- **Agency:** Atlanta Zoning Review Board.
- **Documents Required:**
  - Site plans showing lot size, setbacks, height, and density compliance.
  - Landscape and parking layout plans.
  - Community impact assessment.
- **Approval Timeline:** Usually 6-10 weeks, with public hearings if required.

## 3. Environmental Permits

- **Description:** Permits related to environmental compliance are required to manage stormwater, waste disposal, and other environmental impacts.
- **Agency:** Georgia Environmental Protection Division (EPD).
- **Documents Required:**
  - Environmental Impact Assessment (EIA) report.
  - Erosion and Sediment Control Plan.
  - Stormwater Management Plan.

- **Approval Timeline:** 6-12 weeks depending on scope.

#### 4. Safety and Fire Permits

- **Description:** Permits are required to ensure that the building meets local and federal fire safety standards, including fire exits, alarms, and sprinkler systems.
- **Agency:** Atlanta Fire Rescue Department and Georgia Fire Marshal's Office.
- **Documents Required:**
  - Detailed fire safety plans, including fire exit locations, sprinkler layouts, and alarm systems.
  - Compliance with National Fire Protection Association (NFPA) standards.
- **Approval Timeline:** 4-6 weeks.

#### 5. LEED Certification Documentation

- **Description:** Documentation for LEED Silver certification to meet the project's sustainability and energy efficiency goals.
- **Agency:** U.S. Green Building Council (USGBC).
- **Documents Required:**
  - Energy and water usage plans.
  - Documentation of sustainable materials and building practices.
  - Verification of indoor air quality measures.
- **Approval Timeline:** Certification review can take up to 12 months but can start after construction has progressed sufficiently.

#### 6. Noise Permit

- **Description:** Permits are required to regulate noise levels during construction, especially for any activities outside standard working hours.
- **Agency:** City of Atlanta Noise Control Program.
- **Documents Required:**
  - Noise management plan with details of construction schedule and noise control measures.
- **Approval Timeline:** 2-4 weeks.

#### 7. Accessibility and ADA Compliance Certification

- **Description:** Certification required to ensure that the project meets ADA (Americans with

Disabilities Act) requirements for accessibility.

- **Agency:** Georgia Department of Human Services, ADA Compliance Office.
- **Documents Required:**
  - Architectural plans showing ADA-compliant features, including ramps, elevators, and parking.
  - Detailed layout of accessible units and community areas.
- **Approval Timeline:** Typically reviewed within 4-6 weeks.

## 8. Utility Connection Permits

- **Description:** Permits for connecting the building to essential utilities, including water, sewer, gas, and electricity.
- **Agencies:**
  - Atlanta Watershed Management for water and sewer connections.
  - Local gas and electric utility providers.
- **Documents Required:**
  - Utility connection plans.
  - Utility layout and site drawings.
- **Approval Timeline:** Usually 4-8 weeks depending on service provider availability and site conditions.

## 9. Signage Permit

- **Description:** Required to install any external signage, such as building identification signs and community boards.
- **Agency:** City of Atlanta Department of Planning and Community Development.
- **Documents Required:**
  - Signage design and placement drawings.
  - Details on materials, lighting, and dimensions.
- **Approval Timeline:** Approximately 2-4 weeks.

# Daily/Weekly Progress Reports Template

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

**Date:** [Report Date]

**Report Type:** Daily/Weekly Progress Report

**Prepared by:** Timi Ogunjobi

## 1. Summary of Construction Progress

- **Current Phase:** Structural Work (Week 7 of 10)
- **Milestones Achieved:** Completion of basement levels, ground floor framing 75% complete.
- **Progress Status:** Project is currently on schedule, with 10% of total framing work completed this week.

## 2. Key Activities Completed Today/This Week

- **Basement Concrete Pouring:** Completed on schedule, inspected for quality with no defects.
- **Ground Floor Framing:** 75% completed, minor adjustments made to align with revised design specifications.
- **Electrical Conduits Installation:** Rough-in conduit installation completed for ground floor units.

## 3. Upcoming Activities

- **First-Floor Framing:** Scheduled to begin next week.
- **HVAC Duct Installation:** Preparing for rough-in installation for ground and first floors.
- **Material Delivery:** Steel reinforcement for second floor framing arriving next week.

## 4. Issues and Resolutions

- **Issue:** Delay in ground floor concrete curing due to heavy rains early in the week.
  - **Resolution:** Implemented additional drying and tenting methods. Minor delay mitigated, and work continued without schedule impacts.
- **Issue:** Shortage of electrical conduit materials.
  - **Resolution:** Supplier was contacted to expedite delivery, and extra materials were sourced locally as a temporary measure.

## **5. Safety Observations**

- No incidents reported this week.
- All workers attended daily safety briefings, emphasizing PPE compliance and fall protection.
- OSHA inspection conducted mid-week with no issues found.

## **6. Quality Control Observations**

- Inspections completed for basement concrete and ground floor framing.
- Minor adjustments were required for alignment in the framing, but quality benchmarks were met.
- Material samples for first-floor framing were reviewed and approved.

## **7. Photos and Documentation**

- **Attached Photos:** Ground floor framing progress, electrical conduit installation.
- **Attached Documentation:** Concrete curing report, framing quality inspection notes.

# Safety Management Plan and Safety Log Template

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

**Prepared by:** Timi Ogunjobi

**Date:** [Plan Date]

## 1. Safety Management Plan

**Purpose:** To ensure compliance with OSHA and local safety standards, minimize hazards, and promote a safe working environment for all employees and subcontractors on-site.

## 2. Safety Goals

1. **Zero Accidents and Injuries:** Aim to achieve no recordable incidents throughout construction.
2. **Compliance with OSHA Standards:** Full adherence to OSHA's Construction Safety and Health Program.
3. **Training and Awareness:** Continuous training on-site hazards, proper equipment handling, and emergency procedures.

## 3. Safety Procedures

- **Personal Protective Equipment (PPE):** All personnel must wear hard hats, high-visibility vests, steel-toe boots, and safety goggles.
- **Fall Protection:** Workers performing tasks above 6 feet are required to use fall protection systems (e.g., harnesses, guardrails).
- **Heavy Machinery Operation:** Only licensed operators are permitted to operate heavy machinery, and spotters must be present during operation.
- **Daily Safety Meetings:** Briefings are conducted each morning to discuss daily activities, potential hazards, and preventive measures.
- **Emergency Procedures:** Emergency evacuation plans are displayed, and weekly drills are conducted to ensure quick response in case of incidents.

## 4. Safety Inspections and Monitoring

- **Daily Inspections:** Safety officer conducts site inspections at the start of each day to verify compliance with safety standards and PPE usage.

- **Weekly OSHA Compliance Checks:** Weekly audits ensure all work practices adhere to OSHA regulations.
- **Incident Reporting:** Any incident or near-miss must be immediately reported, documented, and investigated.

5. Safety Log

Log Date: [Date]

Inspector: Timi Ogunjobi

Date	Hazard	Description	Corrective Action	Status
[Date]	Slippery Floor	Rain caused a slippery surface	Installed temporary anti-slip mats	Resolved
[Date]	Inadequate Fall Protection	No guardrails in new framing area	Installed guardrails	Resolved
[Date]	Electrical Safety	Loose wires near walkway	Secured wires with conduit clamps	Resolved
[Date]	PPE Non-Compliance	Workers without goggles in cutting area	Conducted PPE training, enforced compliance	Ongoing

6. Safety Performance Metrics

- **Incidents to Date:** 0
- **Near Misses to Date:** 1 (documented and reviewed)
- **PPE Compliance Rate:** 98% based on daily inspections



# Quality Assurance/Quality Control (QA/QC) Report

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

**Date of Inspection:** [Inspection Date]

**Prepared by:** [QA/QC Manager's Name]

## 1. Summary of Quality Inspections

- **Current Phase:** Ground Floor Framing and Conduit Installation.
- **Quality Standards:** The project adheres to Atlanta's building codes and LEED Silver standards. This inspection focused on framing accuracy, material quality, and electrical conduit installation.

## 2. Quality Control Activities

Item	Quality Standard	Inspection Result	Corrective Action
Ground Floor Framing	Alignment within 1/8 inch	Minor misalignment noted	Realigned sections
Electrical Conduit Installation	Secure every 3 feet	Secured as per standard	N/A
Concrete Basement Floor	Smooth surface, no cracks	Surface smooth, minor curing issue observed	Re-cured with additional drying methods
Insulation Materials	Minimum R-Value of 21	Verified R-Value met standard	N/A

## 3. Material Quality Check

- **Framing Materials:** Lumber inspected for grade and size, with quality meeting the specifications. No warping or defects observed.
- **Electrical Conduit:** Approved as per local electrical codes; installed with proper fastening intervals.
- **Concrete Quality:** Curing progress documented. Minor delay observed but resolved using additional drying.

## 4. Quality Assurance Procedures

- **Daily Inspections:** Conducted for framing accuracy, secure installation of conduits, and concrete curing progress.
- **Third-Party Inspections:** Engaged third-party concrete testing for additional validation of basement floor quality.

- **Documentation:** Daily log entries made for all quality assurance activities, with corrective actions recorded in the QA/QC tracker.

## 5. Observations and Notes

- **Positive Observations:** Installation quality is high, with no major deviations from the project's quality standards. All materials inspected were compliant with LEED and local code standards.
- **Issues Noted:** Minor curing delay for basement concrete due to weather; resolved with adjusted curing methods. No further impact expected.
- **Additional Notes:** Minor alignment issue in the framing was corrected without delay.

## 6. Follow-Up Actions

- **Re-Inspection:** Framing alignment to be re-checked before progressing to upper floors.
- **Additional Curing Checks:** Basement floor to undergo additional inspection for curing strength in 48 hours.

# Risk Assessment and Risk Management Plan

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

**Prepared by:** Timi Ogunjobi

**Date:** 07/02/2021

## 1. Risk Assessment

The risk assessment involves identifying potential risks, assessing their likelihood and impact, and prioritizing them based on their overall threat to the project. For each risk, a risk rating (High, Medium, or Low) is provided.

Risk Category	Risk Description	Likelihood	Impact	Risk Rating
Market Risks	Economic downturn reduces demand for residential rentals, impacting occupancy rates and revenue.	Medium	High	High
Construction Risks	Material shortages or price increases affect project budget and timeline.	High	High	High
	Delays in site preparation due to unforeseen soil or structural issues.	Medium	Medium	Medium
Environmental Risks	Inclement weather disrupts construction activities, especially during foundation and structural work.	Medium	High	High
	Environmental compliance issues due to local regulations (e.g., stormwater management, air quality controls).	Low	Medium	Low
Regulatory Risks	Delays in permits or approvals from city authorities impact project start and timeline.	Medium	High	High
Safety Risks	Accidents or injuries on-site, leading to delays, fines, or legal issues.	Medium	High	High
Operational Risks	Energy-efficient systems (e.g., HVAC, solar) fail to meet performance expectations, increasing maintenance costs.	Medium	Medium	Medium
Financial Risks	Unforeseen costs exceed the project's contingency budget, requiring additional funding.	Medium	High	High
Quality Risks	Quality issues or rework due to contractor errors or non-compliance with specifications.	Medium	High	High
Supply Chain Risks	Delays in material delivery, especially for imported or custom items, impact the construction schedule.	Medium	Medium	Medium

## 2. Risk Management Plan

The risk management plan outlines strategies for mitigating each identified risk. The plan includes risk mitigation actions, monitoring procedures, and escalation measures if necessary.

### 1. Market Risks

- **Risk:** Economic downturn reduces demand for residential rentals, impacting occupancy rates and revenue.
  - **Mitigation Strategy:**
    - Perform a market analysis at regular intervals to monitor demand trends and adjust leasing and pricing strategies as necessary.
    - Establish flexible leasing terms to attract a broader tenant demographic.
  - **Monitoring:** Quarterly reviews of local real estate and rental market data.
  - **Escalation:** If demand drops significantly, involve senior management to consider additional marketing or tenant incentives.

### 2. Construction Risks

- **Risk:** Material shortages or price increases affect project budget and timeline.
  - **Mitigation Strategy:**
    - Establish contracts with multiple suppliers to secure materials at fixed prices where possible.
    - Maintain a buffer stock for critical materials and increase monitoring of material supply schedules.
  - **Monitoring:** Weekly review of material inventory and lead times; regular communication with suppliers.
  - **Escalation:** If materials are delayed by more than two weeks, re-evaluate the project timeline and adjust labor schedules.
- **Risk:** Delays in site preparation due to unforeseen soil or structural issues.
  - **Mitigation Strategy:**
    - Conduct detailed site assessments and geotechnical surveys before breaking ground.

- Allocate contingency funds specifically for unexpected site conditions.
- **Monitoring:** Initial soil tests and weekly site assessment updates during excavation.
- **Escalation:** Report any structural issues to project management immediately for prompt resolution.

### 3. Environmental Risks

- **Risk:** Inclement weather disrupts construction activities, especially during foundation and structural work.
  - **Mitigation Strategy:**
    - Develop a flexible construction schedule with buffer time for weather-related delays.
    - Utilize temporary weather protection measures such as tents or tarps during vulnerable construction phases.
  - **Monitoring:** Daily weather reports; on-site monitoring during heavy rainfall or extreme conditions.
  - **Escalation:** Adjust timelines for critical path activities if inclement weather causes more than two days of delay.
- **Risk:** Environmental compliance issues due to local regulations.
  - **Mitigation Strategy:**
    - Hire an environmental consultant to oversee compliance with stormwater and air quality regulations.
    - Develop an Environmental Impact Management Plan and conduct regular site inspections.
  - **Monitoring:** Monthly environmental compliance checks and reporting.
  - **Escalation:** Immediately address compliance issues with corrective actions if flagged by inspectors.

### 4. Regulatory Risks

- **Risk:** Delays in permits or approvals from city authorities impact project start and timeline.
  - **Mitigation Strategy:**
    - Engage with local authorities early in the project to understand regulatory requirements.
    - Assign a dedicated team member to track permit statuses and expedite approvals as needed.

- **Monitoring:** Weekly updates on permit statuses with a checklist for approvals.
- **Escalation:** Notify project sponsors and legal advisors if delays threaten critical timelines.

## 5. Safety Risks

- **Risk:** Accidents or injuries on-site, leading to delays, fines, or legal issues.
- **Mitigation Strategy:**
  - Implement a Safety Management Plan aligned with OSHA standards and provide regular safety training.
  - Conduct daily safety briefings and enforce Personal Protective Equipment (PPE) use.
- **Monitoring:** Daily safety logs and weekly safety audits.
- **Escalation:** Any injury or major incident will trigger an investigation and immediate corrective action.

## 6. Operational Risks

- **Risk:** Energy-efficient systems (e.g., HVAC, solar) fail to meet performance expectations, increasing maintenance costs.
- **Mitigation Strategy:**
  - Select energy systems with proven reliability and long-term warranties.
  - Test systems during the commissioning phase to verify functionality and compliance with LEED requirements.
- **Monitoring:** Quarterly performance assessments during the initial post-construction phase.
- **Escalation:** If systems underperform, engage with vendors to troubleshoot and, if necessary, replace components under warranty.

## 7. Financial Risks

- **Risk:** Unforeseen costs exceed the project's contingency budget, requiring additional funding.
- **Mitigation Strategy:**
  - Maintain a 10% contingency fund and regularly review budget variances.
  - Review contracts for fixed prices where possible, especially for materials and subcontracted services.

- **Monitoring:** Monthly budget reviews and variance analysis.
- **Escalation:** Inform project sponsors if cost overruns exceed 5% of the total budget, allowing time to secure additional funds if necessary.

## 8. Quality Risks

- **Risk:** Quality issues or rework due to contractor errors or non-compliance with specifications.
- **Mitigation Strategy:**
  - Establish a Quality Assurance and Quality Control (QA/QC) plan with regular inspections and detailed quality standards.
  - Hold contractors accountable for quality by including penalty clauses for repeated issues in contracts.
- **Monitoring:** Weekly inspections during critical construction phases; ongoing QA/QC logs.
- **Escalation:** If quality issues persist, arrange additional training for the team or replace non-compliant contractors.

## 9. Supply Chain Risks

- **Risk:** Delays in material delivery, especially for imported or custom items, impact the construction schedule.
- **Mitigation Strategy:**
  - Pre-order long-lead items and negotiate priority status with key suppliers.
  - Use local suppliers where possible to reduce reliance on imports.
- **Monitoring:** Weekly tracking of material deliveries and supplier performance.
- **Escalation:** Alert the project manager if delays exceed one week, allowing adjustments in the schedule or sourcing alternative materials.

## 3. Risk Monitoring and Reporting

- **Risk Register:** The project manager maintains a detailed risk register, documenting all risks, mitigation actions, and status updates. The register is reviewed and updated monthly.
- **Regular Reviews:** Bi-weekly risk review meetings with the project team to identify emerging risks and evaluate the effectiveness of mitigation strategies.
- **Escalation Procedures:** Critical risks with potential to impact the project timeline or budget are escalated to the project sponsor and key stakeholders. These are assessed in real-time,

and additional resources are allocated if necessary.

#### **4. Key Roles and Responsibilities**

- **Project Manager:** Oversees risk management, ensures risk mitigation strategies are implemented, and updates the risk register.
- **Safety Officer:** Manages safety risks, conducts daily inspections, and reports any incidents immediately.
- **QA/QC Manager:** Monitors quality risks and conducts regular inspections to prevent rework or compliance issues.
- **Procurement Manager:** Manages supply chain risks, tracks material deliveries, and coordinates with suppliers.
- **Project Sponsor:** Engaged for critical risk escalation and financial approval if additional resources are required.



## RACI Matrix

**Project Title:** Residential Apartment Row Development in Buckhead, Atlanta

**Prepared by:** Timi Ogunjobi

**Date:** 07/02/2021

Task/Deliverable	Project Manager	Construction Team	Architect	QA/QC Manager	Safety Officer	Procurement Manager	Project Sponsor
<b>1. Project Initiation</b>	A	R	C	I	I	I	A
<b>1.1 Develop Project Charter</b>	A	I	I	I	I	I	R
<b>1.2 Define Project Scope</b>	A	C	R	I	I	I	A
<b>2. Planning Phase</b>	A	R	C	C	C	C	A
<b>2.1 Develop Project Schedule</b>	R	I	C	I	I	C	A
<b>2.2 Budget Planning</b>	A	I	I	I	I	R	A
<b>2.3 Risk Management Planning</b>	R	C	I	C	C	I	A
<b>2.4 Quality Management Plan</b>	R	I	C	A	I	I	A
<b>2.5 Safety Management Plan</b>	C	I	I	I	A	I	A
<b>3. Permits and Approvals</b>	A	I	R	I	I	R	A
<b>3.1 Building Permits</b>	C	I	A	I	I	R	A
<b>3.2 Environmental Permits</b>	C	I	I	I	I	I	A
<b>3.3 Zoning Approval</b>	C	I	A	I	I	R	A
<b>4. Design Phase</b>	I	I	A	C	I	I	A
<b>4.1 Finalize Architectural Design</b>	C	I	A	I	I	I	A
<b>4.2 Structural &amp; MEP Design</b>	C	I	A	I	I	I	A
<b>5. Procurement Phase</b>	I	I	I	I	I	A	C
<b>5.1 Material Procurement</b>	I	I	I	I	I	A	C
<b>5.2 Contractor Selection</b>	C	A	I	C	C	A	C

Task/Deliverable	Project Manager	Construction Team	Architect	QA/QC Manager	Safety Officer	Procurement Manager	Project Sponsor
<b>6. Construction Phase</b>	A	R	C	C	A	C	I
<b>6.1 Site Preparation</b>	A	R	C	I	C	C	I
<b>6.2 Foundation Work</b>	A	R	C	I	C	C	I
<b>6.3 Structural Work</b>	A	R	C	I	C	C	I
<b>6.4 Install MEP Systems</b>	A	R	C	I	C	C	I
<b>6.5 Framing and Roofing</b>	A	R	C	I	C	C	I
<b>7. Quality Control</b>	A	C	I	R	I	I	I
<b>7.1 Conduct Inspections</b>	A	I	I	R	I	I	I
<b>7.2 Final Quality Assurance Check</b>	A	I	I	R	I	I	A
<b>8. Safety Management</b>	C	R	I	I	A	I	I
<b>8.1 Daily Safety Briefings</b>	I	R	I	I	A	I	I
<b>8.2 Safety Compliance Audits</b>	I	I	I	I	A	I	I
<b>9. Stakeholder Communication</b>	A	I	I	I	I	I	R
<b>9.1 Progress Reports</b>	R	C	I	I	I	I	A
<b>9.2 Issue Resolution Updates</b>	R	C	I	C	C	I	A
<b>10. Project Closeout</b>	A	R	C	C	C	C	A
<b>10.1 Final Inspection</b>	A	R	C	A	I	I	A
<b>10.2 Handover Documentation</b>	R	I	I	C	I	C	A
<b>10.3 LEED Certification Submission</b>	R	I	C	I	I	C	A